- o If stormwater basins or conveyances are proposed for locations within known or potential areas of contamination, coordinate with the District Environmental Manager to determine ways to avoid impacts and prevent the contamination of groundwater and surface water through such stormwater systems. Avoidance measures such as relocations, redesign to reduce cut, etc. are to be considered. If avoidance is not feasible, methods for preventing the spread of contamination are to be considered.
- o The Project Manager will communicate to District Environmental Manager any substantial changes in grades, alignment, stormwater management features and subsurface utilities, especially those changes made late in project development. 

  o

Listed below are some sources which have potential for hazardous material waste from underground tanks or associated sources. This is a partial list and should not be taken as all inclusive. The surveyor should use common sense as well as research information as well as their working knowledge of the areas to be surveyed in order to determine sites with potential underground tanks.

## **Possible Underground Tank Locations:**

Airports Banks

Churches and/or cemeteries Construction Companies

(Fire and Police Dept., Prisons, etc.) Delivery Services (UPS, FedEx, etc.)

**Dry Cleaners** 

Farms

Home Owners Hotels/Motels

Installations and Offices Manufacturing Plants Mining Companies

Residential Apartment Buildings

Service Stations
Tire Stores
Truck Stops
Utility Companies

Auto Dealers and Repair Shops

Car washes

Colleges/Schools/Education Facilities

**Government Services Offices** 

Convenience Stores Distribution Companies

**Engraving Firms** 

Federal and State Government Hospitals and Nursing Homes

**Grocery Stores** 

Jobber Bulk Terminal

Marinas

Recreational Facilities

Restaurants Shopping Centers Transportation Services

**Trucking Firms** 

\_

<sup>&</sup>lt;sup>⋄</sup> Changes to Hazardous Materials/Waste Sites made from IIM-LD191.2 April 2014

<sup>&</sup>lt;sup>⋄</sup> April 2014