

**hydraulic openings equivalent to 12.6 square feet and larger, and for all closed systems such as storm sewers, and sanitary sewers regardless of size:** The Department will stake all such installations. Certified Plats for these stakeouts will be furnished to the Contractor prior to the Contractor beginning work on these culvert structures. The notes, or computations used to support the platted information will be furnished to the Contractor with the certified plat. For the purposes of identifying those pipe culvert installations please refer to the areas (hydraulic openings) shown in the PB-1 Standards for the respective sizes of pipes specified on the plans. Where multiple lines of pipes are shown, the areas of the pipe sizes will apply to the total areas of the number of lines specified in the plans. For box culverts refer to the sizes shown in the BC-1 Standards to determine areas of total hydraulic openings.

- (5) **Horizontal and Verticals Control for Pipe Culvert installations (including single and multiple line installations) having total hydraulic openings equivalent to 3.1 square feet and up to 12.5 square feet:** The Department will be responsible for staking horizontal and vertical controls for pipe culvert installations having a total hydraulic opening equivalent to 3.1 square feet and up to 12.5 square feet. Sketches will be furnished to the Contractor prior to the Contractor beginning work on these culvert structures. For the purposes of identifying those pipe culvert installations please refer to the areas (hydraulic openings) shown in the PB-1 Standards for the respective sizes of pipes specified on the plans. Where multiple lines of pipes are shown, the areas of the pipe sizes will apply to the total areas of the number of lines specified in the plans. For box culverts refer to the sizes shown in the BC-1 Standards to determine areas of total hydraulic opening.
- (6) **Grading and paving construction:** The Department will provide fine grade or other grade stakes required for the construction of all projects except as stated herein as the work progresses. Slope stakes are not required on “M” projects.

Fine grade stakes will be set on all projects on which the plans show a definite grade line. Fine grade hubs will be set on at least one side with distances and grades referenced to the finished centerline grade. Typically, on curves, the Department will provide the distances and elevations to each edge of pavement and centerline through the transitions and the distances and elevations to the edge of pavement only (straight-line super) through full super portions of the curve.

On projects where grading and paving is performed under the same contract, only one set of fine grade stakes will be provided by the Department.. Fine grade stakes may be used for fine grade and paving grade.