APPENDIX K

VDOT Stormwater Management Maintenance Program

2004 VDOT SWM Facilties Maintenance Program

Detention, Retention, and Impoundment BMPs Operation and Maintenance Checklist (3 of 3)

Bioretention Operation and Maintenance Checklist (2 of 2)

Infiltration BMP Operation and Maintenance Checklist (2 of 2)

Environmental Policy for Maintenance of Ditches and Shoulders

Property Owner Agreement – Maintenance Disposal Site

Disposal Areas – DEQ MOA

2004

VDOT STORMWATER MANAGEMENT FACILITIES MAINTENANCE PROGRAM

1. Background

The Virginia Stormwater Management Regulations are mandatory for all state agency land development projects which disturb greater than one acre. These regulations require that appropriate actions be taken to prevent an increase in the 2-year and 10-year discharge as a result of land disturbing activities such as highway construction and maintenance. The regulations also require the capture and treatment of the first half inch of run-off during a storm event. A further regulatory requirement mandates that all stormwater management facilities must be maintained in perpetuity.

2. Maintenance Program

I. Regulatory Information

The regulations require:

- 1) A description of the requirements for maintenance of stormwater management facilities and a recommended schedule of inspection and maintenance.
- 2) The identification of a person or persons who will be responsible for the maintenance of these facilities.
- 3) VDOT is permitted to annually submit its stormwater management standards, specifications and criteria for approval by the Regulatory Agency. This annual submission must address the above noted maintenance aspects.

II. Types of Facilities

There are 3 basic types of stormwater management facilities that will be constructed and must be maintained. Each facility is basically site specific and, therefore, the maintenance requirements for each will be tailored to the specific situation.

- 1) A description of the requirements for maintenance of stormwater management acilities and a recommended schedule of inspection and maintenance.
- 2) Detention facilities usually consist of an impounding structure (dam) and a holding basin. Detention facilities are "dry" basins that contain stormwater only during the run-off event and for a comparatively short period (2 days) after the run-off event. The outlet works in the impounding structure are carefully designed to meet the water outflow requirements of the regulations. It is essential that the function of the outlet works and the volume of the holding basin be maintained as designed.
- 3) Retention facilities structurally resemble detention facilities but are "wet" basins, that is, they maintain a permanent pool of water in the holding basin.

4) Infiltration facilities are stormwater management facilities which temporarily impound run-off and discharge it via infiltration through the surrounding soil. While an infiltration facility may also be equipped with an outlet structure to discharge impounded run-off, such discharge is normally reserved for overflow and other emergency conditions. Since an infiltration facility impounds run-off only temporarily, it is normally dry during non-rainfall periods.

III. Maintenance and Inspection Requirements

1) <u>Inspection</u>

Stormwater management facilities must be inspected semiannually and after any storm event which causes the capacity of the facility to be exceeded. The inspection shall determine the capability of the facility to perform as originally designed. Where the inspection indicates that the structure has been damaged, the facility has collected excessive sediment, or the facility is overgrown with vegetation etc., maintenance will be performed in an expeditious manner to preserve the operating characteristics of the facility.

2) Documentation

Three separate Operations and Maintenance Checklists are provided as attachments to this document. Each Checklist corresponds to the specific facility type requiring inspection and/or maintenance.

IV. Implementation

1) Responsibility

- (a) The Resident Engineer shall be responsible party for the maintenance of stormwater management facilities in each respective Residency.
- (b) The Resident Engineer's identification will be furnished to the Regulatory Agency in accordance with the requirements of the Regulations.
- (c) Field personnel are encouraged to work cooperatively with the Regulatory Agency's field personnel in resolving individual questions concerning the maintenance of stormwater management facilities.
- (d) Questions concerning the applicability of the Regulations or design features of cstormwater management facilities should be directed to the District Hydraulics Engineer in the respective District Office and/or the State Hydraulics Engineer in the Central Office.

(e) Questions concerning the inspection, performance, inventory, and maintenance of stormwater management facilities should be directed to the District Maintenance Engineer in the respective District Office and/or the Roadside Operations Program Manager in the Central Office.

2) Schedule

- (a) Stormwater management facilities shall be inspected semiannually and after any storm event which causes the capacity of the facility to be exceeded.
- (b) Accumulated sediment in stormwater management facilities will be removed when it reaches the designated volume specified on the SWM Facility Maintenance Inspection Checklist.
- (c) Vegetation will be controlled so that it does not inhibit the operation of the stormwater management facility. Debris resulting from vegetation control shall be removed from the facility and disposed of in an approved manner.
- (d) VDOT will be responsive to the request of the field agents of the Regulatory Agency in the maintenance of its stormwater management facilities.

Operation and Maintenance ChecklistPage 1 of 3

	_	_		1 450 1 51 5
	YES / NO	REPAIR	INVESTIGATE	Inspector Name:
Item				Comments
I. EMBANKMENT				
A. Crest				
1. Visual settlement				
2. Misalignment3.				
4. Cracking				
B. Upstream slope				
1. Erosion				
2. Adequate groundcover				
3. Trees, shrubs or other				
5. Cracks, settlements or bulges				
6. Rodent holes				
C. Downstream slope				
1. Erosion				
2. Adequate groundcover				
3. Trees, shrubs or other				
4. Cracks, settlements or bulges				
5. Rodent holes				
D. Abutments				
1. Erosion				
2. Seepage				
3. Cracks				

Operation and Maintenance ChecklistPage 2 of 3

B				1 age 2 of 3
	YES / NO	REPAIR	INVESTIGATE	Inspector Name: Inspection Date: Type of BMP:
E. Drainage, seepage control				
1. Internal drains flowing				
2. Seepage at toe				
II. EMERGENCY SPILLWAY				
1. Eroding or backcutting				
2. Obstructed				
3. Leaking				
4. Operational				
III. PRINCIPAL SPILLWAY BARREL				
 Seepage i nto conduit 				
3. Debris present				
4. Displaced or offset joints				
IV. OUTLET PROTECTION/ STILLING BASIN				
1. Obstructed				
2. Adequate riprap				
3. Undercutting at outlet				
4. Outlet channel scour				
V. BASIN & UPLAND BUFFER AREA				
A. Low flow channel				
1. Erosion				
2. Adequate vegetation				
3. Obstructed				

Operation and Maintenance Checklist Page 3 of 3

				8
	YES/NO	REPAIR	INVESTIGATE	Inspector Name:
B. Basin bottom & side slopes				
1. Erosion				
2. Adequate stabilization				
3. Sediment accumulation				
4. Floating debris				
5. High water marks				
6. Shoreline protection				
C. Inflow channels/pipes				
1. Erosion				
2. Adequate stabilization				
3. Undercutting				
D. Sediment forebay				
1. Sediment accumulation				
2. Stable overflow into basin				
E. Upland landscaping				
F. Aquatic landscaping				

BIORETENTION APPENDIX 3E

Date	Time			
Project	Site Plan / SUP Number			
Location				
Date Placed in Service:	Date of La	st Inspection:		
Individual Conducting the Inspection				
(Owner)				
"As Built" Plans available: Y/N				
Bioretention Facility Type: Infi	ltration;	Filter;	Green Alley	
Warning: If filtration facility has a watertight gases within the facility. Care should be taken that are not vented. If filtration facility is in a convented of the procedures must be followed	lighting a match	or smoking while insp	ecting facilities	
		Satisfactory	Unsatisfactory	
Debris cleanout Contributing areas clean of debris Bioretention facility clean of debris Inlets and outlets clear of debris				
2. Drainage Area Stabilization Contributing drainage area stabilized No evidence of erosion Area mowed and clippings removed				
3. Oil and grease No evidence of filter surface clogging				
Activities in drainage area minimize oil & grease entry				
4. Overflow Structure Overflow grate/throat clear of debris Any grates are in good condition No evidence of erosion (if draining into a natura	l channel)			

BIORETENTION APPENDIX 3E

Operation and Maintenance Inspection Checklist Page 2 of 2

Site Plan / SUP Number	Date:	_			
5. Bioretention Planting Soil	Satisfactory	Lingatiofootomy			
No evidence of planting soil erosion Bioretention basin clean of sediments	Satisfactory	Unsatisfactory			
6. Organic Layer					
Mulch covers entire area (NO voids) and to specified Mulch is in good condition	thickness				
7. Plants					
Specified number and types of plants still in place No dead or diseased plants No evidence of plant stress from inadequate watering No evidence of deficient stakes or wires					
NOTE: Diseased plants must be treated by a qualified profest Dead plants or plants diseased beyond treatment must be replied New plants must be watered every day for the first 14 days at occur following this period.	aced by plants meeting original design spe	ecifications.			
Action to be taken:					
If any of the answers to the above items are checked unsatisfic correction or repair.	actory, a time frame shall be established for	or their			
No action necessary. Continue routine inspections Correct noted facility deficiencies by					
Facility repairs were indicated and completed. Site reinspection is necessary to verify corrections or repairs					
Site reinspection accomplished on					
Site reinspection was satisfactory. Next routine inspection is scheduled for approximately:					
Signati	ire of inspector				

Operation and Maintenance Checklist Page 1 of 2

Date			
Project Location	Site Plan / SU Date Placed in		
Date of Last:	Inspector		
Owner/Owner's Representative			
"As Built" Plans available: Y/N			
1. Debris cleanout		Satisfactory	Unsatisfactory
Contributing areas clean of debris Bioretention facility clean of debris Inlets and outlets clear of debris			
2. Vegetation			
Contributing drainage area stabilized No evidence of erosion Area mowed and clippings removed			
3. Clogging			
Overflow grate/throat clear of debris Observation well clear of water within 48 hrs	of storm event		
4. Structural components			
No evidence of structural deterioration Any grates are in good condition No evidence of spalling or cracking of structural parts			

Operation and Maintenance Checklist Page 2 of 2

Site Plan / SUP Number	Date:		
5. Outlets/overflow spillway		Satisfactory	Unsatisfactory
Good condition, no need for repair No evidence of erosion (if draining into a	a natural channel)		
6. Overall function of facility			
No evidence of flow bypassing facility No standing water			
Action to be taken:			
If any of the answers to the above items are check correction or repair.	ked unsatisfactory, a time f	rame shall be established for	their
No action necessary. Continue routine Correct noted facility deficiencies by	inspections	<u> </u>	
Facility repairs were indicated and completed. Si	te reinspection is necessary	to verify corrections or repa	irs
Site reinspection accomplished on			
Site reinspection was satisfactory. Next routine in	nspection is scheduled for a	approximately:	
	Signatur	e of inspector	

ENVIRONMENTAL POLICY FOR MAINTENANCE OF DITCHES AND SHOULDERS

§1.1 General Provisions:

- 1) As maintenance for ditch and shoulder operations are planned, it is strongly recommended that the soil disposal areas be pre-selected, the property owner agreements be obtained, and erosion and sediment control sketches and narrative be prepared.
- 2) Any maintenance activity disturbing more than 2,500 square feet (232 m2) (length of ditch or shoulder x width of ditch or shoulder = sq. ft.) within any consecutive 30 calendar day period within the area of Tidewater, Virginia, as defined in the Virginia Chesapeake Bay Preservation Act, must have a project specific erosion and sediment control plan and narrative developed for review and approval by the district environmental section and implemented in accordance with the VDOT standards and specifications. Tidewater, Virginia is defined as the counties of Accomack, Arlington, Caroline, Charles City, Chesterfield, Essex, Fairfax, Gloucester, Hanover, Henrico, Isle of Wight, James City, King George, King and Queen, King William, Lancaster, Matthews, Middlesex, New Kent, Northhampton, Northumberland, Prince George, Prince William, Richmond, Spotsylvania, Stafford, Surry, Westmoreland and York and the Cities of Alexandria, Chesapeake, Colonial Heights, Fairfax, Falls Church, Fredericksburg, Hampton, Hopewell, Newport News, Norfolk, Petersburg, Poquson, Portsmouth, Richmond, Suffolk, Virginia Beach and Williamsburg.
 - If operations are performed in localities not listed above the E&S Plan is required for land disturbance greater than 10,000 sq. ft.
 - The E&S controls must be installed prior to or concurrent with the land disturbing operation.
 - Where original root systems are disturbed Ditches and shoulders shall be stabilized as recommended by the District Roadside Manager.
 - If the disposal occurs within the same drainage area as the excavation, the square footage impacted by both activities shall be added to determine E&S requirements.
 - The E&S plan for the disposal area must consider minimum standard #19 of the Virginia Erosion and Sediment Control Regulations where appropriate, for receiving channels.
- 3) The district environmental section shall review the disposal area site when there is the possibility wetlands or stream impacts
- 4) Unless the excavated materials are going directly to a landfill, all visible trash shall be removed from the ditch both prior to excavation and following disposition of

- materials. Consideration should be made in coordinating operations with local Adopta-Highway volunteers or prison inmates
- 5) If obviously contaminated soils are encountered, the district Environmental Section must be notified immediately. Such contamination might include dark or unnaturally stained areas, chemical/petroleum-type odors, or the presence of broken or leaking containers of hazardous materials.
- 6) Materials shall not be placed within 100-feet of any stream, wetland, or other body of water.

§2.0 Specific Provisions:

§2.1 Stockpiling of Excavated Materials at VDOT Maintenance Facilities

- 1) If excavated soil is to be stockpiled at the maintenance facility for later use:
 - A sign shall be erected on the stockpile to prevent dumping of unacceptable materials on the stockpile.
 - The stockpile need not be permanently stabilized until soil is removed. However, if material is left undisturbed for more than 15-days it shall be stabilized with a temporary seed mix as recommended by the District Roadside Manager. Once removed, the area shall be permanently stabilized with a seed mix recommended by the District Roadside Manager unless the stockpile is placed on an impervious surface.

§2.2 Disposal of Excavated Materials on VDOT rights-of-way:

 Soil or rock being disposed of shall be established on a maximum 2:1 slope and permanently stabilized with a seed mix recommended by the District Roadside Manager.

§2.3 Disposed of Excavated Materials on Private Property:

- The maintenance superintendent shall ensure that materials are not placed on the site until all approvals are received. These approvals may include permits from local government and local E & S reviews.
 - "The boundaries (perimeter) of the disposal site shall be clearly marked. Acceptable marking methods are stakes, ribbons, flags, spray paint, etc."
- A property owner agreement must be executed prior to placement of any material. The agreement and other related documentation shall remain on file atthe residency for 3-years after completion.
- Maintenance superintendent or district environmental section shall photograph the site before materials are placed and as final permanent stabilization is complete.

• Soil or rock beign disposed of shall be established on a maximum 3:1 slopes and permanently stabilized with a seed mix recommended by the District Roadside

§2.4 Disposal of Excavated Materials at a licensed landfill:

• Disposal of excavated materials at landfill is allowable, however, consideration should be made as to disposal costs. Attempts should be made to have the landfill accept the materials at no charge for use as daily cover.

PROPERTY OWNER AGREEMENT MAINTENANCE DISPOSAL SITE

	on of Project:	Route(s)		County			
Date			Property Owner				
	I hereby grant permission to dispose of material which consists of topsoil, dirt, and gravel from the above referenced maintenance project onto my property at the following location						
				area as needed for completion of this e Virginia Erosion and Sediment Control			
the cor	I will be responsible for any and all grading of the disposal material. VDOT will be responsible for the control of erosion in compliance with the Virginia Erosion and Sediment Control Law and Regulations for the disposal area and haul road, if any unless otherwise specified below.						
Comm arising	I also agree to release and hold harmless the Virginia Department of Transportation, the Commonwealth of Virginia, and its employees from responsibility for damages and all liabilities arising from the use of my property to dispose of excess material from the above reference maintenance project.						
Owner Owner	or Authorized Agent	t of the		Date			
1000							
I agree	llowing to be comp to provide and m	aintain the follo	owing erosion and	ne presence of a VDOT representative: sediment control measures to comply 1-560 et seq. of the Code of Virginia and			
				on and Sediment Control Regulations):			
			bilization to all denuded s without working on the	d areas within seven days after grading is he site.			
	During placement of	material place and	d maintain erosion and	sediment control measures.			
	Apply permanent stal	bilization within or	ne year if left dormant u	unless used for agricultural purposes.			
	Install perimeter trapp	ping devices as a	first step in the deposit	t of material.			
	stabilization.			es within 30-days of establishment of permanent			
Any ite	ins not checked w	viii de the respi	onsibility of VDOT.				

Disposal Areas

Based on Memorandum of Agreement with Virginia Department of Environmental Quality And Current Solid Waste Regulations

Materials that cannot be disposed of in a disposal area:

- Antifreeze
- Asphalt (liquid)
- Building forms
- Concrete with exposed rebars
- Curing compound
- Fuel
- Hazardous materials
- Limbs
- Lubricants
- Metal
- Metal pipe
- Oil
- Paint
- Stumps
- Tree trunks
- Wood or metal from building demolition

Materials that may be disposed of in an approved disposal area:

- Asphalt (solid)
- Brick
- Cinder block
- Concrete (without exposed rebars)
- Dirt
- Rock

<u>Disposal areas located on VDOT rights-of-way</u> must be covered with 2-feet of clean material, placed on a maximum 2:1 slope, and seeded with the seed mix recommended on the Roadside Development Sheet or with a recommendation from the Transportation Roadside Development Manager. If the area is predominately wet or has plants that appear to be wetland species – have the District Environmental Section look at it before placement of materials.

<u>Disposal areas located on private property</u> must be covered with 2-feet of clean material placed on a maximum 3:1 slope and seeded with the seed mix recommended on the Roadside Development Sheet or with a recommendation from the Transportation Roadside Development Manager. If the area is predominately wet or has plants that appear to be wetland species avoid placement of material.

<u>Stumps</u> should not be buried either on or off state rights of way. However, if they are buried solid and vegetative waste regulations must be followed. These include:

- Notification of all adjoining property owners 14-days prior to opening thevegetative waste disposal site.
- Survey of site before material is buried and record in local courthouse.
- Survey at time of closure showing location of all materials buried, recording with property information in local courthouse.
- Notification of all adjoining property owners within 48-hours of closure.
- Installation of groundwater and methane gas monitoring wells.
- Monitoring materials collected in wells and reporting annually to Virginia Department of Environmental Quality on findings.
- Providing corrective measures should pollutants be detected in wells.

<u>Stumps and tree trunks (non-merchantable timber)</u> may be ground into mulch, stockpiled, and beneficially used. If stockpiled, the pile must be reduced by 75% within 12-months. Ground chips may be given away for use as mulch or fuel. Ground chips may be used to stabilize bare areas, however, they should not be piled more than 2-inches in depth if used for this purpose.