

VIRGINIA DEPARTMENT OF TRANSPORTATION  
2007 ROAD AND BRIDGE SUPPLEMENTAL SPECIFICATIONS

**SUPPLEMENTAL DIVISION I—GENERAL PROVISIONS**

**Section 107.16(a) Erosion and Siltation** of the Specifications is amended to replace the fourth paragraph with the following:

For projects that disturb 10,000 square feet or greater of land or 2,500 square feet or greater in Tidewater, Virginia, the Contractor shall have within the limits of the project during land disturbance activities, an employee certified by the Department in Erosion and Sediment control who shall inspect erosion and siltation control devices and measures for proper installation and operation and promptly report their findings to the Inspector. Inspections shall include all areas of the site disturbed by construction activity and all off site support facilities covered by the project's Stormwater Pollution Prevention Plan. Inspections shall be conducted at least once every 14 calendar days and within 48 hours following any runoff producing storm event (Note: If an inspection is conducted as a result of a storm event, another inspection is not required for 14 calendar days following provided there are no more runoff producing storm events during the that period). For those areas that have been temporarily stabilized or runoff is unlikely to occur due to winter conditions (e.g., the site is covered with snow or ice or frozen ground exists), inspections shall be conducted at least once a month. Those definable areas where final stabilization has been achieved will not require further inspections provided such areas have been identified in the project's Stormwater Pollution Prevention Plan. Failure of the Contractor to maintain a certified employee within the limits of the project will result in the Engineer suspending work related to any land disturbing activity until such time as a certified employee is present on the project. Failure on the part of the Contractor to maintain appropriate erosion and siltation control devices in a functioning condition may result in the Engineer notifying the Contractor in writing of specific deficiencies. Deficiencies shall be corrected immediately. If the Contractor fails to correct or take appropriate actions to correct the specified deficiencies within 24 hours after receipt of such notification, the Department may do one or more of the following: require the Contractor to suspend work in other areas and concentrate efforts towards correcting the specified deficiencies, withhold payment of monthly progress estimates, or proceed to correct the specified deficiencies and deduct the entire cost of such work from monies due the Contractor. Failure on the part of the Contractor to maintain a Department certified erosion and sediment control employee within the project limits when land disturbance activities are being performed will result in the Engineer suspending work related to any land disturbance activity until such time as the Contractor is in compliance with this requirement.