

(e) **Storm Water Pollution Prevention Plan and Virginia Stormwater Management Program General Permit for the Discharge of Stormwater from Construction Activities**

A Stormwater Pollution Prevention Plan (SWPPP) identifies potential sources of pollutants which may reasonably be expected to affect the stormwater discharges from the construction site and any off site support areas and describes and ensures implementation of practices which will be used to reduce pollutants in such discharges.

The SWPPP is comprised of, but not limited to, the Erosion and Sediment Control (ESC) Plan, the Stormwater Management (SWM) Plan and related Specifications and Standards contained within all contract documents and shall be required for all land-disturbing activities that disturb 10,000 square feet or greater, or 2,500 square feet or greater in Tidewater, Virginia.

Land-disturbing activities that disturb 1 acre or greater, or 2500 square feet or greater in an area designated as a Chesapeake Bay Preservation Area, require coverage under the Department of Conservation and Recreation's Virginia Stormwater Management Program (VSMP) General Permit for the Discharge of Stormwater from Construction Activities (hereafter referred to as the VSMP Construction Permit). Where applicable, the Department will apply for and retain coverage under the VSMP Construction Permit for those land disturbing activities for which it has contractual control.

The required contents of a SWPPP for those land disturbance activities requiring coverage under the VSMP Construction Permit are found in Section II D of the General Permit section of the VSMP Regulations (4VAC50-60-1170). While a SWPPP is an important component of the VSMP Construction Permit, it is only one of the many requirements that must be addressed in order to be in full compliance with the conditions of the permit.

The Contractor and all other persons that oversee or perform activities covered by the VSMP Construction Permit shall be responsible for reading, understanding, and complying with all of the terms, conditions and requirements of the permit and the project's SWPPP including, but not limited to, the following:

**1. Project Implementation Responsibilities**

The Contractor shall be responsible for the installation, maintenance, inspection, and, on a daily basis, ensuring the functionality of all erosion and sediment control measures and all other stormwater and pollutant runoff control measures identified within or referenced within the SWPPP, plans, Specifications, permits, and other contract documents.

The Contractor shall take all reasonable steps to prevent or minimize any stormwater or non-stormwater discharge that will have a reasonable likelihood of adversely affecting human health or public and/or private properties.

**2. Certification Requirements**

In addition to satisfying the personnel certification requirements contained herein, the Contractor shall certify his activities by completing, signing, and submitting Form C-45 VDOT SWPPP Contractor and Subcontractor Certification Statement to the Engineer at least 7 days prior to commencing any project related land-disturbing activities, both on-site and off-site.

### 3. **SWPPP Requirements for Support Facilities**

Where not included in the plans, the Contractor shall develop erosion and sediment control plan(s) and stormwater pollution prevention plan(s) for submission and acceptance by the Engineer prior to usage of any on-site or off-site support facilities including but not limited to, borrow and disposal areas, construction and waste material storage areas, equipment and vehicle storage and fueling areas, storage areas for fertilizers or chemicals, sanitary waste facilities and any other areas that may generate a stormwater or non-stormwater discharge directly related to the construction process. Such plans shall document the location and description of potential pollutant sources from these areas and shall include a description of the controls to reduce, prevent and control pollutants from these sources including spill prevention and response. The Contractor shall submit such plans and documentation as specified herein to the Engineer and, upon review and approval, they shall immediately become a component of the project's SWPPP and VSMP Construction Permit (where applicable) and shall be subject to all conditions and requirements of the VSMP Construction Permit (where applicable) and all other contract documents.

### 4. **Reporting Procedures**

#### a. **Inspection Requirements**

The Contractor shall be responsible for conducting inspections in accordance with the requirements herein. The Contractor shall document such inspections by completion of Form C-107 (a) and (b), Construction Runoff Control Inspection Form and Continuation Sheet, in strict accordance with the directions contained within the form.

#### b. **Unauthorized Discharge Requirements**

The Contractor shall not discharge into state waters sewage, industrial wastes, other wastes or any noxious or deleterious substances nor shall otherwise alter the physical, chemical, or biological properties of such waters that render such waters detrimental for or to domestic use, industrial consumption, recreational or other public uses.

##### (1). **Notification of non-compliant discharges**

The Contractor shall immediately notify the Engineer upon the discovery of or potential of any unauthorized, unusual, extraordinary, or non-compliant discharge from the land disturbing activity. Where immediate notification is not possible, such notification shall be not later than 24 hours after said discovery.

##### (2). **Detailed report requirements for non-compliant discharges**

The Contractor shall submit to the Engineer within 5 days of the discovery of any actual or potential non-compliant discharge a written report describing details of the discharge to include its volume, location, cause, and any apparent or potential effects on private and/or public properties and state waters or endangerment to public health, as well as steps being taken to eliminate the discharge. A completed Form C-107 (a) and (b) shall be included in such reports.

## **5. Changes, Deficiencies and Revisions**

### **a. Changes and Deficiencies**

The Contractor shall report to the Engineer when any planned physical alterations or additions are made to the land disturbing activity or deficiencies in the project plans or contract documents are discovered that could significantly change the nature or increase the quantity of the pollutants discharged from the land disturbing activity to surface waters.

### **b. Revisions to the SWPPP**

Where site conditions, construction sequencing or scheduling necessitates revisions or modifications to the erosion and sediment control plan or any other component of the SWPPP for the land disturbing activity, such revisions or modifications shall be approved by the Engineer and shall be documented by the Contractor on a designated plan set (Record Set).

Such plans shall be maintained on the project site or at a location convenient to the project site where no on site facilities are available and shall be available for review upon request during normal business working hours.