



Notes:

Anchor bolts and bolt pattern shall be furnished with pole. Pole shall be centered on foundation.

Each foundation shall be permanently marked to indicate all sides from which conduits pass. This mark shall be made with a trowel when finishing the concrete and shall be 1/4" deep and 4" to 6" long. Locations of empty conduits shall have an additional 2" long mark made perpendicular to and centered on this marking.

When foundation extends 4" above finished grade all edges shall be chamfered 3/4".

Grounding bushings shall be installed on each end of metal conduits. Empty conduits shall be plugged to prevent moisture and rodent entry.

Bell ends shall be installed on each end of PVC conduits. Empty conduits shall be plugged to prevent moisture and rodent entry.

Open ends of conduits with conductors installed shall be sealed with an approved soft, pliable, and easily removable waterproof sealant. The sealant shall have no deleterious effect on cable coverings.

No mortar, grout, or concrete shall be placed between bottom of base plate and top of pedestal.

SIGNAL POLE FOUNDATION
 INSTALLATION DETAILS
 VIRGINIA DEPARTMENT OF TRANSPORTATION