

(R10) Date: September 23, 2013	Proj.: 0360-964-120, RW-201, C-501
Changes in quantities as a result of revision dated September 23, 2013	
Changes in Quantities:	
Increase:	
36 TONS	Asphalt Concrete Type SM-12.5D
26 TONS	Asphalt Concrete Type IM-19.0D (T)
23 TONS	Aggr. Base Material Type I No. 21B
Decrease:	
265 SY	Median Strip St'd. MS-1
89 LF	Storm Sewer Pipe 15"
64 LF	Storm Sewer Pipe 18"
16 LF	15" Conc. Pipe
3.7 LF	Manhole MH 1 or 2
Add:	
74 TONS	Crusher Run Aggr. 25 or 26
1 EA	Drop Inlet DI-3B, L=10'
1 EA	Drop Inlet DI-3B, L=14'
Remove:	
1 EA	Drop Inlet DI-1
1 EA	Drop Inlet DI-3B, L=12'
1 EA	Inlet Protection, Type A
This revision was made in accordance to memorandum from Mr. John Kennedy (Project Manager) and Mr. Sam Hayes (Asst. Dist. Admin. PE) dated August 9, 2013.	
THIS IS A PORTION OF A SAMPLE SHEET, FOR A CURRENT VERSION, ACCESS THE CELL LIBRARY Sheet2000.cel.	

FIGURE 2G-3 REVISION DATA SHEET (CONSTRUCTION)*