

On Secondary Road projects, fine grade stakes will be provided by the Department only on those projects having curb and gutter or as directed by the Engineer.

Special design ditches will be staked with an offset and cut to the centerline of the ditch. Radius points for pavement flares at connections will be staked only if requested by the Contractor.

(7) Right of way and boundary stakeout affecting property ownership:

Right of Way will be staked by the Department prior to the start of the job.

The right of way stakes will be placed at a minimum of 100-foot intervals on each side of the roadway or as directed by the Engineer and the stakes will be marked with both the station and offset back to centerline. All final boundary stakeout will be performed by the Department survey party.

(8) Setting right-of-way monuments: Final right of way monumentation will be performed by the Department in accordance with the following:

- a) RM-1: The Department will furnish and install RM-1 right-of-way monuments in accordance with the Road and Bridge Standards.
- b) RM-2: The Department will furnish and install RM-2 right-of-way monuments and optional locator posts, including the required caps, in accordance with the Road and Bridge Standards.
- c) Other monumentation: The Department will determine if an alternative form of permanent monumentation will be used if RM-1 or RM-2 monuments are unsuitable for marking the right-of-way at various locations. The Department will indicate this alternative monument usage on the final as-built plan in accordance with the Department's Survey Manual.