

Sec. 8.12 No-Plan Projects

No-plan projects typically require very limited survey effort and this is addressed in the contract by copied note “c105a0b-0702”.

Sec. 8.13 Minimum Plan Projects

Minimum Plan projects are either covered by Section 105.13 and 517 of the Road and Bridge Specifications or in the contract by Special Provision c105a0b-0702.

Sec. 8.14 Condemnation Staking

Condemnation stakeouts will be performed by the Department and are not to be performed by the Contract Surveyor for the project.

On all condemnation stakeouts, the following color codes will be used:

Limited Access Line	Mark with Blue
Proposed Right-of-way	Mark with Red
Existing Right-of-way	Mark with White
Permanent Easement	Mark with Green
Temporary Easement	Mark with Orange
Utilities	Mark with Yellow

Sec. 8.15 As-built Plan of Right-of-way Monumentation

On projects where right of way monumentation is a plan quantity, an “As-Built” plan needs to be submitted.

Once construction has been completed and all R/W monumentation has been set, the VDOT Surveyor is responsible for an “As-built” survey of the right of way as required in Section 105.13 and 517 of the Road and Bridge Specifications. An example of what survey information is expected in the completed “As-Built” drawing is shown in Chapter 8, [Figure 4](#).

Sec. 8.16 Submitting Survey Data

As soon as the project is complete the Contract Survey should submit all survey notes, electronic files, and required “sealed” drawings to the Project Inspector. This information will be reviewed by the District Survey Manager, and upon his approval that the survey information submitted meets all requirements, he will recommend to the Resident Engineer whether final payment should be made or if additional information should be required.