

(c301a0b-0503) **SECTION 301.02—PROCEDURES** is amended to replace the first paragraph with the following:

If approved by the Engineer, the Contractor may clear and grub to accommodate construction equipment within the right of way up to 5 feet beyond the construction limits at his own expense. The Contractor shall install erosion and siltation control devices prior to beginning clearing or grubbing operations and such devices shall be functional before upland land-disturbing activities take place.

1-27-03 (SPCN)