

Where a sequence of construction plan is considered unnecessary for a particular project, the file shall be documented accordingly with the listing of the names of those involved in the decision and the reasons for the decision.

The Field Inspection prints must also indicate that a sequence of construction plan is not necessary and that only such items as flagging, warning lights, etc., will be required.

All of the above items are to be discussed thoroughly at the Field Inspection and recommendations included in the Field Inspection Report.

REQUEST FOR SPECIAL DESIGN DRAWINGS*

After the Field Inspection questions have been resolved, requests shall be made to the [Standards/Special Design Section](#), to prepare the necessary special design roadway drawings for inclusion in the plans. This process is explained in [Section 2G-1-FINALIZING PLANS](#) of this manual.

If circumstances dictate a change in the plans that would alter or eliminate the need for a special drawing that is in the process of being prepared, the [Standards/Special Design Section](#) is to be notified immediately.

* Rev. 1/19