$CDATE $REF01 $REF02 $REF03 $REF04 $REF05 $REF06

$CDATE1 $LEV01 $LEV02 $LEV03 $LEV04 $LEV05 $LEV06

PROJECT MANAGER (Project Mgr. Name, 1000) 000-0000 (District)
SURVEYED BY (Surveyor Name 1000) 000-0000 (District)
DESIGN SUPERVISED BY (Supervisor Name, 1000) 000-0000 (District)
DESIGNED BY (Designer Name 1000) 000-0000 (District)

REVISED	STATE	STATE ROUTE	STATE PROJECT	SHEET NO.
	VA.	00	0000-000-000, RW-000 C-000	0

DESIGN FEATURES RELATING TO CONSTRUCTION OR TO REGULATION AND CONTROL OF TRAFFIC MAY BE SUBJECT TO CHANGE AS DEEMED NECESSARY BY THE DEPARTMENT

'95 CADD LEVEL STRUCTURE

SURVEY

NOTE: Survey Utility Information will be in a separate file.
Digital Terrain Model Information will be separate files.

LEVEL 1	CENTERLINE, TRAVERSE, CONTROL STATION
LEVEL 2	BRIDGES
LEVEL 3	EDGE OF PAVEMENT
LEVEL 4	CURB AND GUTTER
LEVEL 5	CURB
LEVEL 6	PAVED SHOULDER
LEVEL 7	SIDEWALK
LEVEL 8	BUILDINGS, PORCHES
LEVEL 9	WALLS
LEVEL 10	STEPS
LEVEL 11	FENCES
LEVEL 12	WOOD LINE, TREES, SHRUBS, HEDGE, POPS
LEVEL 13	RETAINING WALLS
LEVEL 14	CONCRETE SLABS, COLUMNS, SIGNS, POSTS
LEVEL 15	TANKS
LEVEL 16	GUARDRAILS
LEVEL 17	EDGES OF WATER
LEVEL 18	PAVED DITCHES
LEVEL 19	DRAINAGE ITEMS (MANHOLES, CATCH BASINS, SHOP INLETS, SQUARE PIPES)
LEVEL 20	RAILROADS, ETC.
LEVEL 21	SEPTIC TANKS, DRAIN FIELDS, WELLS
LEVEL 22	CEMETERIES
LEVEL 23	POINT OF NEW AND POINT OF NEW ELEMENTS
LEVEL 24	PROPERTY LINES AND PROPERTY PINS
LEVEL 25	STATE, COUNTY, AND CITY BOUNDARY LINES
LEVEL 26 - 30	NOT ASSIGNED
LEVEL 31 - 36	MODIFICATION FOR LEVELS 1-25
LEVEL 37 - 60	NOT ASSIGNED
LEVEL 61	PLAN SHEET, NORTH ARROW, SCALE BAR, ETC.
LEVEL 62	GRID AND LABELS
LEVEL 63	NOT ASSIGNED

TRAFFIC ENGINEERING

LEVEL 1	EXIST. STREET CONDUCTOR CABLE (SIGNALIZATIONS & CONTROLLER CABINETS)
LEVEL 2	EXIST. SIGNAL HEADS, PEDESTRIAN HEADS, EXIST. BALANCER ASSEM., SPAN WIRE, SIGNAL POLES, PEDESTRIAN PUSHBUTTONS, LUMINAIRES & LUMINAIRE ARMS
LEVEL 3	EXIST. PARKING DIAGONALLY, STRAIGHT, CHART, EXTENDED CHART, TRAFFIC CHART & DESIGN SYMBOLS
LEVEL 4	EXIST. SIGN PANELS, STRUCTURES & LUMINAIRES
LEVEL 5	EXIST. DELINEATORS
LEVEL 6	EXIST. HIGH MAST LIGHTING STANDARD, OFFSET LIGHTING STANDARD & CONVENTIONAL LIGHTING STANDARD
LEVEL 7	EXIST. ELECTRICAL SERVICE, METER BOXES & SAFETY SWITCHES
LEVEL 8	EXIST. PAVEMENT MARKINGS & PAVEMENT MARKERS
LEVEL 9	NOT ASSIGNED
LEVEL 10	NOT ASSIGNED
LEVEL 11	EXIST. CONDUIT TEST & CONDUCTOR CABLE TEST
LEVEL 12	LABELING OF EXISTING SIGNAL EQUIPMENT
LEVEL 13	LABELING OF EXIST. SIGNAL CHARTS & DIAGRAMS
LEVEL 14	LABELING OF EXIST. SIGN STRUCTURES
LEVEL 15	LABELING OF EXIST. DELINEATORS
LEVEL 16	LABELING OF EXIST. LIGHTING STANDARDS
LEVEL 17	PROPOSED CONDUIT CONDUCTOR CABLE (SIGNALIZATIONS & CONTROLLER CABINETS)
LEVEL 18	PROPOSED SIGNAL HEADS, PEDESTRIAN HEADS, EXIST. BALANCER ASSEM., SPAN WIRE, SIGNAL POLES, PEDESTRIAN PUSHBUTTONS, LUMINAIRES & LUMINAIRE ARMS
LEVEL 19	PROPOSED PARKING DIAGONALLY, STRAIGHT, CHART, EXTENDED CHART, TRAFFIC CHART & DESIGN SYMBOLS
LEVEL 20	PROPOSED SIGN PANELS, STRUCTURES & LUMINAIRES
LEVEL 21	PROPOSED DELINEATORS
LEVEL 22	PROPOSED HIGH MAST LIGHTING STANDARD, OFFSET LIGHTING STANDARD & CONVENTIONAL LIGHTING STANDARD
LEVEL 23	PROPOSED ELECTRICAL SERVICE, METER BOXES & SAFETY SWITCHES
LEVEL 24	PROPOSED PAVEMENT MARKINGS & PAVEMENT MARKERS
LEVEL 25 & 26	NOT ASSIGNED
LEVEL 27	PROPOSED CONDUIT TEST & CONDUCTOR CABLE TEST
LEVEL 28	LABELING OF PROPOSED SIGNAL EQUIPMENT
LEVEL 29	LABELING OF PROPOSED SIGNAL CHARTS & DIAGRAMS
LEVEL 30	LABELING OF PROPOSED SIGN STRUCTURES
LEVEL 31	LABELING OF PROPOSED DELINEATORS
LEVEL 32	LABELING OF PROPOSED LIGHTING STANDARDS
LEVEL 61	BASE PLAN SHEET, SCALE BAR, NORTH ARROW, ETC.

DESIGN

LEVEL 1	BASELINE & SUBTAMENTS
LEVEL 2	BRIDGES
LEVEL 3	EDGE OF PAVEMENT & PAVEMENT ENTRANCES
LEVEL 4	CURB AND GUTTER
LEVEL 5	CURB
LEVEL 6	PAVED SHOULDER
LEVEL 7	SIDEWALK AND/OR BICYCLE TRAIL
LEVEL 8	NOT ASSIGNED
LEVEL 9	NOT ASSIGNED
LEVEL 10	STEPS
LEVEL 11	FENCES
LEVEL 12	DIRECTIONAL ARROWS, PAVEMENT STAMPING & FLUSH BERMS DELINEATOR
LEVEL 13	RETAINING WALLS
LEVEL 14	CONCRETE SLABS, COLUMNS, SIGNS, POSTS
LEVEL 15	NOT ASSIGNED
LEVEL 16	GUARDRAIL & JERSEY BARRIER
LEVEL 17	NOT ASSIGNED
LEVEL 18	PAVED DITCHES
LEVEL 19	RESERVED FOR MISCELLANEOUS ITEMS TO BE PLACED IN ROAD DESIGNER
LEVEL 20	RAILROADS, ETC.
LEVEL 21	NOT ASSIGNED
LEVEL 22	LIMITS OF CONSTRUCTION
LEVEL 23	POINT OF NEW TEMP. & PERMANEMENTS
LEVEL 24	NOT ASSIGNED
LEVEL 25 - 30	NOT ASSIGNED
LEVEL 31 - 54	MODIFICATION FOR LEVELS 1-25
LEVEL 55 - 60	NOT ASSIGNED
LEVEL 61	BASE PLAN SHEET, SCALE BAR, NORTH ARROW, ETC.
LEVEL 62	NOT ASSIGNED
LEVEL 63	NOT ASSIGNED

TRAFFIC ENGINEERING

LEVEL 1	PIPES FROM 4" TO 42"
LEVEL 2	PIPES 42" AND LARGER
LEVEL 3	STANDARD BOX CULVERTS
LEVEL 4	ENDWALLS
LEVEL 5	END SECTIONS
LEVEL 6	PAVED DITCHES AND FLUMES
LEVEL 7	EXISTING DRAINAGE PIPE, SPLITTER AND SPRING BOXES
LEVEL 8	MANHOLES AND JUNCTION BOXES
LEVEL 9	DROP INLETS DI-1, DI-3 AND DI-5 SERIES
LEVEL 10	DROP INLETS DI-7 SERIES
LEVEL 11	DROP INLETS DI-1 SERIES
LEVEL 12	DROP INLETS DI-1 SERIES
LEVEL 13	DROP INLETS DI-7 SERIES
LEVEL 14	DROP INLETS DI-5 SERIES
LEVEL 15	DROP INLETS DI-1 SERIES
LEVEL 16	DROP INLETS DI-2 SERIES
LEVEL 17	SPECIAL DESIGN ITEMS (HEADWALLS, INLETS, ETC.)
LEVEL 18	EXISTING CONTROL DITCH ITEMS (RIP RAP, ETC.)
LEVEL 19	EXISTING CONTROL STRUCTURE (RIP RAP, FLOW DIVERSION)
LEVEL 20	EXISTING CONTROL STRUCTURE (DITCH, FLOW DIVERSION)
LEVEL 21	MISCELLANEOUS ESS ITEMS
LEVEL 22	SEW BASIN ITEMS (BASIN, INLETS, PIPE, ETC.)
LEVEL 23	SEW BASIN (CONTOURS)
LEVEL 24	SEW BASIN MISCELLANEOUS ITEMS
LEVEL 25	UNDERDRAINS (CONNECTIONS, LINES, ETC.)
LEVEL 26	UNDERDRAIN OUTLET PIPE AND DI-2 INLET (ETC.)
LEVEL 27	TYPICAL DITCH DETAILS
LEVEL 28 - 30	NOT ASSIGNED
LEVEL 31 - 60	MODIFICATION FOR LEVELS 1-30
LEVEL 61	SHEET, NORTH ARROW, ETC.
LEVEL 62	NOT ASSIGNED
LEVEL 63	PROJECT NOTES

PROJECT	SHEET NO.
0000-000-000	0

$FILENAME