

SECTION 511—ALLAYING DUST

511.01—Description

This work shall consist of applying either moisture, calcium chloride, or both on areas designated by the Engineer for the purpose of allaying dust.

511.02—Procedures

The Contractor shall furnish a truck(s) equipped with a water tank having a capacity of at least 1,000 gallons and pumps for furnishing, loading, and applying water to the roadway.

Equipment and operators shall be available at all times.

Calcium chloride conforming to the requirements of Section 239 shall be applied at the rate specified on the plans or by the Engineer.

The Contractor shall plan and prosecute the work so as to expedite completion of the pavement structure as soon as is practicable.

511.03—Measurement and Payment

Allaying dust will be measured and paid for on the basis of the time the truck is in service on this work or per ton of calcium chloride. Loading time allowed for payment shall be not more than 30 minutes per 1,000 gallons of water. Truck hours shall be evidenced by daily time reports submitted by the Contractor and approved by the Engineer. This price shall include water and calcium chloride.

When in-place base material is used as a riding surface to maintain traffic or as a haul route, truck hours or tons of calcium chloride used for allaying dust will be paid for in accordance with the provisions herein.

Payment will be made under:

Pay Item	Pay Unit
Allaying dust	Hour or Ton