

Example Plan Quantity Items

Any item, whether on the example list or not, should be designated as a plan quantity item only after consultation with the District Construction Engineer.

ITEM	SPEC	ITEM DESCRIPTION	UNITS
00120	303	REGULAR EXCAVATION *	C.Y.
00111	301	CLEARING AND GRUBBING	ACRE
00211	303	MINOR STRUCTURE EXCAVATION PIPE CULVERT	C.Y.
00212	303	MINOR STRUCTURE EXCAVATION BOX CULVERT	C.Y.
00490	302	CLASS I BACKFILL MATERIALS	TON
00491	302	CLASS I BACKFILL MATERIALS	CY
00492	302	CLASS II BACKFILL MATERIALS	TON
00493	302	CLASS II BACKFILL MATERIALS	CY
00500	302	BEDDING MATERIAL FINE AGGREGATE.	TON
00502	302	BEDDING MATERIAL FINE AGGREGATE OR AGGREGATE NO. 10	TON
00504	302	BEDDING MATERIAL FINE AGGREGATE OR AGGREGATE NO. 8	TON
00505	302	BEDDING MATERIAL AGGREGATE NO. 25 OR 26	TON
00522	302	CONCRETE CLASS A4 BOX CULVERT	C.Y.
00540	302/406	REINFORCED STEEL	LB.
11020	316	CONCRETE CLASS A4 BRIDGE APPROACH SLAB	C.Y.
11030	316	REINFORCED STEEL BRIDGE APPROACH SLAB	LB.
13250	504	BEDDING MATERIAL.	TON
13251	504	BEDDING MATERIAL.	C.Y.
13545	406	REINFORCED STEEL	LB.
13561	401	POROUS BACKFILL	C.Y.
13565	506	RETAINING WALL EXCAVATION	506
13580	417	DAMPPROOFING	S.Y.
13750	519	SOUND WALL COLOR COATING	S.F.
13753	519	SOUND BARRIER WALL	S.F.
13754	519	PRECAST SOUND BARRIER WALL	S.F.
13755	519	PRECAST SOUND BARRIER WALL ABSORTIVE	S.F.
24400	508	OBSCURING ROADWAY	UNIT
24410	508	DEMOLITION OF PAVEMENT	S.Y.
24420	508	DEMOLITION OF PAVEMENT (RIGID)	S.Y.
24430	508	DEMOLITION OF PAVEMENT (FLEXIBLE)	S.Y.
69805	416	WATERPROOFING	L.F.
69810	417	DAMPROOFING	S.Y.

Regular Excavation is listed per VDOT [Road and Bridge Specifications](#), Section 303.06(c).