

The **Diversion**\* are to be set up in separate summaries as follows:

Type A and B

Temporary **Diversion**, Standard GS-10

Location	Type "A" (Feet)	Type "B" (Feet)
Route 601 (Sta. 100+00)	550'	
Route 602 (Sta. 150+00)		625'
Route 604 (Sta. 250+00)	655'	
Route 605 (Sta. 300+00)	560'	
Totals	1765'	625'

Type C through F

Temporary **Diversion** St'd. GS-10 Type "E"

Route 606 (Sta. 350+00)

1233 Cu. Yds.	Regular Excavation
* 223 Lin. Ft.	18" Pipe
* 112 Lin. Ft.	30" Pipe
222 Cu. Yds.	Aggregate Base Mat'l. Ty. I No. 21 or 21A (6" Depth)
100 Tons	Asphalt Concrete Type SM-2A @ 165 lbs/yd <sup>2</sup>

\*Set up pipes for payment only when recommended by the Drainage Section.

The quantities for a Type "C", "D", "E", or "F" **Diversion** are to be shown separately, as above, but are to be combined with the mainline quantities on the estimate and bidding proposal.